

East of Hudson Watershed Corporation Kent-MB-1000 Addendum #2

July 15, 2025

The following is a list of clarifications and/or changes to the bid documents subsequent to issuance of the bid package based on the Requests for Information received:

RFI Questions / Responses

- 1. Can the woodchips remain onsite or do they need to be removed?
 - Woodchips from tree felling may be used for construction and maintenance of the temporary construction access paths during construction. If used for the temporary construction access paths, the woodchips may remain in place. Stabilization of the channels and other areas of disturbance with the exception of the temporary construction access paths shall be in accordance with the project drawings. Woodchip mulch stabilization will not be accepted for soil disturbance on slopes exceeding 3H:1V or where erosion control matting is shown. Any excess woodchips stockpiled onsite shall be removed at the expense of the contractor.
- 2. Is the contractor expected to bring in topsoil.

Topsoil onsite within the limits of disturbance shall be striped and stockpiled onsite. The topsoil stockpiles shall be spread upon completion of all grading operations and stabilized with seed and mulch or erosion control matting. The plan is to only utilize what soil is onsite.

ADDENDUM NO. 2

Receipt Acknowledged

Bidders must acknowledge receipt of this addendum by stapling this page to the back of the Bid Sheet.

Bidder:
Legal Name or Person, Partnership, Joint Venture or Corporation
Ву:
Date:

Email a pdf. copy of this receipt to info@eohwc.org

End of Addendum No. 2